whitworth sports feasibility study

Ebenezer Cotts

Cowm House

East View

Path (um)

OAK STREET

OAK CLOSE

SPRING SIDE

Large boulder to restrict vehicular access

Ditch with water running in to River

Japanese Knotweed

Millgate Terrace

A 671

Stone Headwall above River
Some repairs required to fill in holes and support existing culvert wall using 2nd hand stone to match.
All works to be approved by the Environment Agency

Short BMX track
Humps, twists and valleys formed using compacted excavations from site. Layout to be approved by the local children and final compacted stone surfacing approved by them.

Seat

Notice Board/Sign

Markings for 5 a-side football pitch
On mown grass area 20 x 40m with movable steel goal posts

High stone retaining wall
Some minor repairs to secure stones and fill holes using 2nd hand stone.

Back Millgate

Millgate Private Car Park

TCB

255.3m

Large boulder to restrict vehicular access

Oakview Nursing Home

Changing rooms and showers

Car Park

Notice Board/Sign

BIN

Seat

Existing woodland
Dense, woodland to be thinned slightly with criown lifting and some felling around the edges.
Creating improved views in and out of space and more natural surveillance along existing paths.
Some localised post and wire fence repairs.

253.9m

Car Park
For visiting teams.
Space for 21 cars (2 disabled spaces).
Tarmac surface with water drainage in to new gulley system. Enclosed with shrubs and new tree planting and low barriers.
Access from road for pedestrians and coach users parking on side road.

Drained existing pitch
Existing grass pitch to have a combination of Verti Drain and Mains and Lateral land drains installed at 5m intervals in a herringbone layout.
2 No stone headwalls in river bank with outfalls in to River Spodden.
All outfalls, headwalls and drainage consent to be applied for from the Environment Agency.
Low spots to be filled with top soil, cultivated and reseeded.

Leavengreave

Rugby Playing Field

John Henry Street

New Perimeter Path
For casual walkers, dog walkers and rugby spectators.
Surface in compacted recycled stone 2m wide with soft edges merging in with existing grass

Seat

Headwalls

Headwalls
With drainage outlet pipe into River

N

5 15 40m

Notes
1) Figured dimensions to be taken. Do not scale dimensions. Contractors must verify all dimensions on site before preparing shop drawings or commencing any work.
2) Copyright ©. This drawing must not be reproduced without the permission of The Groundwork Trust
3) Reproduced from 1998 Ordnance Survey mapping with permission of the controller of HMSO.

KEY

- Existing grass pitch drained and low spots filled
- Proposed compacted stone path 2m wide
- Car Park area for changing rooms
- Short BMX Track in compacted stone with mounds and valleys, twists and turns
- Seat / Notice Board/Sign — Informal seating, with signs and information about events and community activities
- Proposed pitch drainage withheadwall and outfalls to River
- New tree planting around car park and changing rooms
- New shrub planting around car park
- Existing trees crown lifted and thinned
- BIN — Litter and Dog Bin

00.00.00	REVISION NOTES	ISSUE	CHKD

DESIGN | PLANNING | TENDER | CONTRACT

GROUNDWORK PENNINE LANCASHIRE
The Globe Centre, St. James Square,
Accrington, Lancashire, BB5 0RE
Tel: 01254 265163
Fax: 01254 386816

email: pennine@groundwork.org.uk
www.groundwork.org.uk

CLIENT
Whitworth Town Council

PROJECT
Whitworth Sports Council Feasibility Study
Leavengreave and Back Millgate

TITLE
Improved drained pitch and shorter BMX track

SCALE	DATE	DRAWING NO.
1:500	1.7.09	SC7045/L01

DRAWN BY	CHECKED BY	PROJECT CODE	ISSUE
AD		SC7045	